


PLAN VIEW CIRCULAR OPENING





REINFORCED CONCRETE

SPLIT PIPE OR

TO FIT

SQUARE MANHOLES W/ FLAT TOP

FORM CONCRETE


CONCRETE


MIN. SLOPE

CONSTRUCTION

CAST-IN-PLACE CONCRETE BLOCK WITH CAST-IN-PLACE OR PRECAST REINFORCED CONCRETE BASE

MANHOLES 3X3-FT, 4X4-FT, 5X5-FT AND 6X6-FT





JOINTS TO BE SEALED WITH A BUTYL RUBBER SEAL PER SEALANT MANUFACTURERS TOP WITH TONGUE AND GROOVE JOINT RECOMMENDATIONS CONFORMING TO ASTM C 990 (TYP)

4" OVERHANGING BASE

- PRECAST REINFORCED

CONCRETE FLAT SLAB TOP

1/2" CEMENT PLASTER COAT

SECTION A-A

PLAN VIEW


CAST-IN-PLACE REINFORCED CONCRETE

TOP (SHOWN) OR PRECAST REINFORCED

CONCRETE FLAT SLAB TOP (SEE DETAIL


MATRIX

SECTION B-B



RISER WITH TONGUE AND GROOVE JOINT

DETAIL "B"



SEPARATE PRECAST REINFORCED CONCRETE BASE OPTION

DETAIL "A"

GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

UNLESS OTHERWISE AUTHORIZED IN WRITING BY THE ENGINEER, THE CONTRACTOR SHALL NOT ORDER AND DELIVER PRECAST MANHOLE UNITS REQUIRED FOR THE PROJECT UNTIL A LIST OF SIZES IS FURNISHED BY

DETAILED DRAWINGS FOR PROPOSED ALTERNATE DESIGNS FOR UNDERGROUND DRAINAGE STRUCTURES SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL PROVIDING THAT SUCH ALTERNATE DESIGNS MAKE PROVISION FOR EQUIVALENT CAPACITY AND STRENGTH.

ALL DRAINAGE STRUCTURES ARE DESIGNATED ON THE PLANS AS "MANHOLES 3X3-L", "CATCH BASINS 4-B", "INLETS 2X3-H", ETC. THE FIRST NUMBERS DESIGNATE THE SIZE OF THE STRUCTURE, AND THE FOLLOWING LETTER DESIGNATES THE TYPE OF COVER TO BE USED TO COMPRISE THE COMPLETE UNIT.

BASES SHALL BE PLACED ON A BED OF MATERIAL AT LEAST 6 INCHES IN DEPTH, WHICH MEETS THE REQUIREMENTS OF FOUNDATION BACKFILL. THIS BEDDING SHALL BE COMPACTED AND PROVIDE UNIFORM SUPPORT FOR THE ENTIRE AREA OF THE BASE.

PRECAST REINFORCED FLAT SLAB TOPS MAY BE USED ON CONCRETE BLOCK STRUCTURES.

STEPS MEETING AASHTO M199 AND THE FOLLOWING REQUIREMENTS SHALL BE INSTALLED IN ALL STRUCTURES OVER 5 FEET IN DEPTH: 16 INCH C-C MAXIMUM SPACING; PROJECT A MINIMUM CLEAR DISTANCE OF 4 INCHES FROM THE WALL AT THE POINT OF EMBEDMENT; MINIMUM LENGTH OF 10 INCHES; MINIMUM WALL EMBEDMENT OF 3 INCHES, FERROUS METAL STEPS NOT PAINTED OR TREATED TO RESIST CORROSION SHALL HAVE A MINIMUM CROSS SECTIONAL DIMENSION OF LINCH.

STEPS OF APPROVED POLYPROPYLENE PLASTIC COATED REINFORCEMENT BAR ARE ACCEPTABLE. REINFORCING BAR MUST BE A MINIMUM OF $\frac{1}{2}$ INCH AND MEET THE REQUIREMENTS OF ASTM A615.

CERTIFICATION SHALL BE PROVIDED THAT INSTALLED STEPS WHEN TESTED IN ACCORDANCE WITH SECTION 10 OF AASHTO T280 CAN WITHSTAND A VERTICAL LOAD OF 800 LBS. AND A HORIZONTAL LOAD OF 400 LBS.

ALL BAR STEEL REINFORCEMENT SHALL BE EMBEDDED 2 INCHES CLEAR UNLESS OTHERWISE SHOWN OR NOTED.

CONCRETE BLOCK WILL NOT BE PERMITED FOR STRUCTURES GREATER THAN 4 FEET IN WIDTH.

PRECAST REINFORCED RISERS SHALL HAVE A TONGUE AND GROOVE JOINT WITH TONGUE UP OR DOWN.

ALL PRECAST MANHOLE UNITS SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF ASTM C 913.

4" OVERHANGING BASES ARE REQUIRED FOR ALL CONCRETE BLOCK INSTALLATIONS, 4" OVERHANG IS REQUIRED WHEN SEPARATE PRECAST BASE IS PROVIDED. OVERHANG IS NOT REQUIRED ON PRECAST STRUCTURES WITH AN INTEGRAL OR MONOLITHIC BASE

MAXIMUM PIPE DIAMETER DETERMINED BY 3 INCH CLEARANCE ON EACH SIDE OF THE OUTSIDE WALL OF THE PIPE. SEE DETAIL "C". ASSUMES PIPE ENTERS PERPENDICULAR TO THE STRUCTURE.

- (1) FOR PRECAST MANHOLES PROVIDE REINFORCING STEEL IN ACCORDANCE TO ASTM C 913.
- (2) CONTRACTOR TO PROVIDE DRAWING(S) STAMPED BY A PROFESSIONAL ENGINEER FOR STEEL REINFORCING DESIGN FOR CAST-IN-PLACE STRUCTURES.

MANHOLE COVER OPENING MATRIX

MANHOLE COVER TYPE	С	ALL J'S	К	L	М
OPENING SIZE (FT)					
2 DIA.	Х	×		Х	
3 DIA.			Х		Х

OUTSIDE PIPE WALL
OUTSIDE 3" MIN. (TYP)
PIPE WALL

DETAIL "C"

MANHOLE	MAXIMUM IN DIAMET		
SIZE	WIDTH (IN)	LENGTH (IN)	
3X3-FT	24	24	
4X4-FT	30	30	
5X5-FT	42	42	
6X6-FT	54	54	

PIPE MATRIX

MANHOLES 3X3-FT, 4X4-FT 5X5-FT AND 6X6-FT

STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION

KOV	

	Sept., 2016	/S/ Rodney Taylor
	DATE	ROADWAY STANDARDS DEVELOPMENT
FHWA		UNIT SUPERVISOR

SEE DETAIL "A"

SPLIT PIPE OR

PRECAST REINFORCED

CONCRETE WITH

MONOLITHIC BASE

FORM CONCRETE

O D ∞

Ω

Standard Detail Drawing 8B10

October 3, 2016

Manholes 3x3-FT, 4x4-FT, 5x5-FT, and 6x6-FT

References:

FDM 13-25-15

Bid items associated with this drawing:

ITEM NUMBER	DESCRIPTION	<u>UNIT</u>
611.2033	Manholes 3x3-FT	EACH
611.2044	Manholes 4x4-FT	EACH
611.2055	Manholes 5x5-FT	EACH
611.2066	Manholes 6x6-FT	EACH

Standardized Special Provisions associated with this drawing:

STSP NUMBER TITLE

NONE

Other SDDs associated with this drawing:

SDD 8A5 Inlet cover sheets "b" and "d".

SDD 8D17 Manholes, Manhole and Inlet Covers

Design Notes:

Guidelines for matching manhole opening size and manhole covers are provided on the front side of this SDD.

A pipe matrix on the front side of this SDD provides guidance for selecting the maximum inside pipe diameter. The inside pipe diameter was determined by the pipe entering perpendicular to the structure at 90°. Pipes entering at a skewed angle should be evaluated on a case by case basis.

Manholes should be used as follows:

- 1. For cleaning and maintenance locations spaced as recommended in FDM chapter 13
- 2. At changes in pipe size
- 3. At bends in pipe
- 4. Where flow needs to be split or diverted

Contact Person:

Ed Lilla (608) 266-2312